

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE
REQUEST FOR FILING
(RULE 53(b)(1))

For Design or Utility Applications

Rule 53(b)(1) PATENT APPLICATION:

(DO NOT USE FOR CIPs)

Continuation)
) application under 37 CFR 1.53(b)(1)

Divisional)

of pending prior application of

Group Art Unit: 1306

Examiner: KUHNS

Inventor(s): FORTE

Parent Appln. No.: 08 690,063
 Series Code ↑ Serial No.

Atty. Dkt. PM 251091

DKT95-DIV

New M#

Client Ref

Parent Filed: July 31, 1996

This Case Filed:

Title: MULTILAYER BREATHABLE FILM..BREATHABLE FILM

Date: August 16, 1999

Asst. Commissioner of Patents
 Washington, DC 20231

(Parent Matter No. 217460)

Sir:

To effect the above-requested filing today:

Attached is a copy (**which must be filed**) of this application, including:

- ☒ Abstract
☒ Specification and claims (65 pages) (**must be attached**)
☒ Drawings (**must be attached if originally filed**): 4 sheet(s)/set: ☒ 1 set informal;
☐ Formal of size ☐ A4 ☐ 11"

A. Always X one box, only:

- (1) ☒ Signed declaration or oath as originally filed in prior application attached
 (2) ☐ NO declaration or fee is enclosed; therefore, this is a filing under Rule 53(f).

2. ☐ This application is hereby filed by less than all of the inventors named in the prior application. Petition is hereby made requesting deletion as inventor(s) of the following who is/are **not** inventor(s) of the invention being claimed in this application:

1. _____
 3. _____
 5. _____
 7. _____
 9. _____

2. _____
 4. _____
 6. _____
 8. _____
 10. _____

3. The entire disclosure of the prior application is considered as being part of the disclosure of the accompanying application and is hereby incorporated therein by reference thereto.

4. ☐ Priority is claimed under 35 U.S.C. 119/365 based on filing in _____ of _____ (country)

<u>Application No.</u>		<u>Filing Date</u>	<u>Application No.</u>		<u>Filing Date</u>
(1)	_____	_____	(4)	_____	_____
(2)	_____	_____	(5)	_____	_____
(3)	_____	_____	(6)	_____	_____

a. ☐ _____ (No.) Certified copy/copies attached.

b. ☐ Certified copy/copies previously filed on _____ in _____ U.S. Application No. _____ / _____, filed on _____.

series code ↑ serial no.

c. ☐ Certified copy/copies filed during International stage of PCT/ _____ / _____.

4. (a) ☐ Domestic priority is claimed from PCT/ _____ / _____, filed _____.
- (b) ☒ Benefit is claimed of Provisional Application No. 60/001,818, filed August 1, 1995.

5. ☒ Prior application is assigned to Kimberly-Clark Worldwide, Inc., filed April 1, 1999

by assignment recorded April 6, 1999 Reel 9858 Frame 0004.
(Date)

6. ☒ Attached is the following number of Assignments (including original and all later successive ones by different assignors): 2 and respective new Cover Sheets. (Do **NOT** file old cover sheets.)

(Assignments in parent **must be refiled** with new Cover Sheets in this continuing application if you want it/them recorded against the continuing application.)

Please return the recorded Assignment to the undersigned.

7. ☒ The power of attorney in the prior application is to Pillsbury Madison & Sutro, Paul N. Kokulis Reg. No. 16,773

(Name and Reg. No.)

whose current address is as in item 8 below.

- a. ☒ Recognize as associate attorney Gregory P. Brummett, Reg. No. 41,646

(Name, Reg. No. and Address)

8. **Address all future communications to Intellectual Property Group of Pillsbury Madison & Sutro LLP, Ninth Floor, East Tower 1100 New York Avenue, N.W., Washington, D.C. 20005-3918**

9. ☒ **Amend the specification** by inserting before the first line the sentence:--This is a
☐ continuation ☒ division of Application No. 08/690,063, filed July 31, 1996
series code ↑ serial no.

9. (a) ☒ **Amend the specification** by inserting before the first line: --This application claims the benefit of Provisional Application No. 60/001,818, filed August 1, 1995 .--

10. ☐ It has been recently determined that this new continuing application is entitled to small entity status.
Hence:

(No.) Verified Statement(s) establishing "small entity" status under Rules 9 & 27 were/are:

☐ filed in above prior application (and hence applicable hereto)

☐ attached.

11. Petition to extend the life of the above prior application to at least the date hereof

(one box) ☐ is being concurrently filed in that prior application (Use Form PAT-111).

(must be) ☐ was previously filed in that prior application (Check length of prior extension).

(X'd) ☒ is not necessary for copendency (**Double check** before X'ing this box).

12. ☒ **INFORMATION DISCLOSURE STATEMENT:** Attached is Form PTO-1449 listing all of the documents cited by Applicant and the PTO in the parent application(s) relied upon under 35 USC 120 and referenced in item 9 above. Per Rule 98(d) copies of those documents are not required now. Please consider those documents and advise that they have been considered in this new application as by returning a copy of the enclosed Form PTO-1449 with the Examiner's initials in the left column per MPEP 609. .
13. ☐ Attached is a Rule 103(a) Petition to Suspend Action.
14. ☐ **PRELIMINARY AMENDMENT to be entered before fee calculation:** (Do not make amendments here except for correction of improper multiple dependencies or cancellation of whole claims or multiple dependencies for purpose of reducing the filing fee per MPEP §§ 506 and 607; do not cancel all claims).

FILING FEE

THE FOLLOWING FILING FEE IS BASED ON

->->->->CLAIMS AS FILED AND CHANGED BY PRELIMINARY AMENDMENT IN ITEM 14<-<-<-<-<-

NOTE: If box 1A2 is X'd, do not pay fees,
but leave lines 15-22 and 27-32 blank.

				Large/Small Entity		Fee Code
15. Basic Filing Fee Design Application				\$310/\$155		106/26
16. Basic Filing Fee Not Design Application				\$760/\$380	+760	101/201
17. Total Effective Claims	31	minus 20 =	11	x \$18/\$9	+198	103/203
18. Independent Claims	4	minus 3 =	1	x \$78/\$39	+78	102/202
19. If any proper multiple dependent claim (ignore improper) is present,				\$260/\$130	+	104/204
20.				Subtotal =	\$1036	
21. If "petition" box 13 above is X'd, add petition fee. \$130					+	122
21A. If box 6 above is X'd, add Assignment recording fee \$40					+80	581
22. TOTAL FILING FEE ATTACHED =					\$1116	

(carry forward to Item 31)

23. ☐ ATTACHED:
24. ☒ Preliminary Amendment attached (to be entered after assigning Appln. No.)
25. ☐ The following PRELIMINARY AMENDMENT is to be entered after assigning Appln. No.:

26.

**ADDITIONAL FEE CALCULATION FOR
PRELIMINARY AMENDMENT
PER BOXES 24/25**

	Claims remaining after amendment	Highest number previously paid for	Present Extra	Additional Fee	
					<u>Large/Small Entity</u> <u>File Code</u>
27.	Total Effective Claims	<u>*4</u>	minus ** <u>31</u> = <u>0</u>	x \$18/\$9 = \$ <u>0</u>	(103/203)
28.	Independent Claims	<u>*1</u>	minus *** <u>3</u> = <u>0</u>	x \$78/\$39 = + <u>0</u>	(102/202)
29.	If amendment enters proper multiple dependent claim(s) into this application for the first time, add (per application) \$260/\$130			+ <u>0</u>	(104/204)
30.				ADDITIONAL FEE	\$ <u>0</u>
31.				plus FEE from item 22 on page 3	+ <u>1116</u>
32.				<u>TOTAL FEE ATTACHED</u>	\$ <u>1116</u>

33. *If the entry in this space is less than the entry in the next space, the "Present Extra" result is "0"

34. **If the "Highest number previously paid for" (see item 17 above) is less than 20, write "20" in this space

35. If the "Highest number previously paid for" (see item 18 above) is less than 3, write "3" in this space

Our Deposit Account No. 03-3975

Our Order No. 60707 | 251091
C# M#

CHARGE STATEMENT: Upon the filing of a Declaration pursuant to Rule 60(b) or 60(d), the Commissioner is hereby authorized to charge any fee specifically authorized hereafter, or any missing or insufficient fee(s) filed, or asserted to be filed, or which should have been filed herewith or concerning any paper filed hereafter, and which may be required under Rules 16-18 (missing or insufficient fee only) now or hereafter relative to this application and the resulting Official document under Rule 20, or credit any overpayment, to our Account/Order Nos. shown above for which purpose a duplicate copy of this sheet is attached.

This CHARGE STATEMENT does not authorize charge of the issue fee until/unless an issue fee transmittal form is filed.

**Pillsbury Madison & Sutro LLP
Intellectual Property Group**

1100 New York Avenue, N.W.
Ninth Floor, East Tower
Washington, D.C. 20005-3918
Tel: (202) 861-3000

GPB/blq
Atty./Sec.

By Atty: Gregory P. Brummett

Sig: 

Reg. No. 41,646

Fax: (202) 822-0944

Tel: (202) 861-3683

NOTE No. 1: File this Request in duplicate with 2 postcard receipts (PAT-103) & attachments

NOTE No. 2: Is extension in parent necessary for copendency? **DOUBLE CHECK** Item 11 above.

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re PATENT APPLICATION of

FORTE

DIVISIONAL of Appl. No. 08/690,063

Group Art Unit:

Filed: August 9, 1999

Examiner:

Title: MULTILAYER BREATHABLE FILM AND A METHOD
FOR MAKING A MULTILAYER BREATHABLE FILM

* * * * *

August 16, 1999

PRELIMINARY AMENDMENT

Hon. Commissioner of Patents
and Trademarks
Washington, D.C. 20231

Sir:

Prior to substantive examination of this divisional application, please enter the following amendments and comments.

IN THE TITLE:

Please amend the title to read as follows:

A MULTILAYER BREATHABLE FILM [AND A METHOD FOR MAKING A
MULTILAYER BREATHABLE FILM].

IN THE SPECIFICATION:

At page 1, line 1, please add --This application is a divisional application from
application 08/690,063, filed July 31, 1996.--

08/690,063
FORTE
August 16, 1999

IN THE CLAIMS:

Please cancel claims 1-25 and 30-31.

Please amend claim 26 as follows:

26. A multilayer breathable film having the combination of properties of:

- (i) providing a barrier to microorganisms; and
- (ii) providing a barrier to blood and bodily fluids;

said breathable film comprising at least a three-layer film consisting essentially of
[having as a minimum] the following structure:

C:D:C;

where C comprises an outer monolithic layer containing a hydrophilic polymeric resin capable of absorbing and desorbing moisture and providing a barrier to water and microorganisms, said outer monolithic layer being substantially free of particulate filler; and,

D comprises a microporous adhesive core layer for bonding said outer monolithic layers together, said microporous adhesive core layer containing micropores, wherein said outer monolithic layers substantially prevent the buildup of particulate filler material on a die during formation of said multilayer breathable film, and wherein said micropores are constructed and arranged to provide the passage of gaseous water but substantially prevent the passage of liquid water.

08/690,063
FORTE
August 16, 1999

REMARKS

In light of the above amendments, the applicant respectfully submits that claims 26-29 remain under consideration in the present application. Early action on the merits would be appreciated and is respectfully requested. The applicant also respectfully submits that with the above amendments, claim 26, and dependent claims 27-29, are allowable over the prior art of record in the parent application 08/690,063 and a Notice to that effect is earnestly solicited.

Respectfully Submitted,

Cushman Darby & Cushman
Intellectual Property Group of
PILLSBURY MADISON & SUTRO LLP

By: 

Gregory P. Brummett
Reg. No. 41,646
Tel. No. (202) 861-3683

1100 New York Avenue, N.W.
Ninth Floor
Washington, D.C. 20005
Tel: (202) 861-3000

**MULTILAYER BREATHABLE FILM AND A
METHOD FOR MAKING A MULTILAYER BREATHABLE FILM**

5 Priority to the provisional application
serial No. 60/001,818, filed on August 1, 1995, is
claimed. The complete disclosure of the
provisional application is hereby incorporated by
reference.

10 1. **FIELD OF THE INVENTION**

15 This invention relates to multilayer
breathable films, and more particularly to five-
layer breathable films. The invention also
relates to a method for making multilayer
breathable films.

20 2. **BACKGROUND OF THE INVENTION**

25 Films which allow the transfer of gasses at
moderate to high transmission rates are often
called breathable. The gasses most commonly used
to demonstrate a film's breathability are water
vapor, sometimes referred to as moisture vapor,
and oxygen. The moisture vapor transmission test
(MVTR) and oxygen transmission test (OTR) measure
the mass or volume of gas transported across the
cross section of the film in a given unit of time
30 at a defined set of environmental conditions.
While the mechanism of gas transfer often differs
from film to film, it is the total amount of gas
that passes through the film which makes films
breathable.

35 When in close proximity to the skin, high
MVTR films allow the body to cool itself
naturally. When a high MVTR film also provides a

barrier to liquid transfer and/or microbial transfer, there are a variety of applications, most of which are in direct or indirect contact with skin, that can take advantage of this unique combination of properties.

Potential applications include surgical gowns, bandages, hospital bed pads, disposable diapers, house wrap, feminine napkins, protective clothing, shoe liners, food packaging, and gloves.

Breathable films can be classified as either microporous or monolithic, depending on their physical makeup and their mechanism of gas transfer.

One type of microporous film consists of a blend of polymers and inorganic fillers which are extruded into a film or sheet using standard fabrication techniques. In a secondary step or in the same continuous process with sequential operations, the sheet or film is oriented or stretched in one or two directions at temperatures below the melting point of the polymer. The result of the input of this mechanical energy into the polymer/filler matrix is the creation of numerous interconnected or closely coupled pores which permit the passage of gas molecules. The density and size of these pores can be controlled by both the selection of raw materials and the conditions at which orientation or stretching occurs.

When a functional microporous film is produced it will allow the passage of gas molecules while not allowing the passage of the liquid from which the gas molecules may have originated.

Another type of microporous film, sometimes referred to as a foamed film, contains the same matrix of interconnected or closely coupled pores previously described except these pores are formed by the release of gasses that are formed under certain conditions of temperature and pressure. These films normally contain a conventional polyolefin as the primary component and a foaming and/or nucleating agent as minor components. The foaming agent is a substance which has significantly higher vapor pressure than the polyolefin at extrusion temperatures. The size and density of the pores can be altered by changing extrusion conditions and the type or concentration of the foaming and/or nucleating agents. These films transport gasses using the same mechanism of diffusion as filler oriented microporous film.

Monolithic breathable films are solid homogeneous fluid barriers which transport gasses via at least one of the mechanisms of absorption, adsorption, diffusion or desorption. These polymers are highly hygroscopic. It is their affinity for water that results in absorption of water in water rich environments. And once saturated, these films will pass water molecules to a moisture lean environment. This type of breathable film transfers water vapor much better than it does oxygen or other gasses.

The above breathable films can be combined to form multilayer breathable films. Examples of such multilayer breathable films are described in the following U.S. Patents.

U.S. Patent No. 5,164,258 describes a

multilayer breathable film consisting of outer layers of a breathable hydrophobic material (microporous), a core hygroscopic barrier layer (monolithic), and adhesive layers disposed between the core layer and the two outer layers. This patent teaches that outer monolithic layers do not work because they absorb water and the outer layer expands. See column 2, lines 12-20.

U.S. Patent No. 4,828,556 discloses multilayer breathable film consisting of a polyvinyl alcohol monolithic layer disposed between two microporous non-woven web layers. No adhesive is required because the polyvinyl alcohol acts as both the adhesive and the monolithic layer.

U.S. Patent No. 4,863,788 discloses a multilayer film consisting of a microporous membrane having on one side a continuous film protective layer and on another side a cellular foam adhesive layer and a fabric substrate.

U.S. Patent No. 4,758,239 discloses a multilayer breathable film consisting of a water soluble polymeric (monolithic) layer having on one side a microporous sheet.

U.S. Patent No. 5,143,773 discloses a multilayer film consisting of a water absorbing central layer (monolithic) having on one side a water impermeable layer and on another side a microporous layer.

Typically, the multilayer films are extruded. However, when microporous layers containing a filler material are extruded, the filler material collects on the extruder die and inhibits the extrusion process. Usually, after 30 minutes to

about an hour of use the filler builds up on the extruder die to such an extent that the extruder must be shut down and the filler material mechanically removed from the extruder die. This is very costly and time consuming. Therefore, there is a great need for multilayer film which when extruded does not cause a build-up of filler material on the extruder die.

For some types of multilayer films, the core is typically the thickest layer and makes up the most material by volume. When monolithic materials are utilized these multilayer films, the core layer usually contains the monolithic material. However, the monolithic layer is very expensive compared to microporous materials. Thus, there is a great need for multilayer material which uses significantly less monolithic material yet provides a sufficient barrier against microorganisms and liquids.

Multilayer breathable films having a monolithic layer have been used in medical films to provide a microbiological barrier to prevent microorganisms from penetrating the material and infecting a medical person contained therein. During certain medical procedures such as open heart surgery, significant amounts of blood and internal fluids are ejected onto the medical gowns of medical personnel. It is very important that these liquids and the microorganisms present therein do not penetrate the material where they can infect the medical personnel.

Thus, there is a great need for a multilayer breathable film which provides a good barrier to microorganisms and internal human fluids, which

reduces the amount of monolithic material required, and does not contaminate the extruder die during extrusion.

5

SUMMARY OF THE INVENTION

It is an objective of the present invention to provide a multilayer breathable film which causes significantly reduced contamination of the die with filler material during extrusion.

Another objective of the present invention is to provide a multilayer film that provides a good biological and liquid barrier while significantly reducing the amount of monolithic material required.

A further objective of the invention is to provide a method of making the multilayer breathable film.

The above objectives and other objectives are surprisingly obtained by the following.

The invention provides a novel multilayer breathable film having the of properties of:

- (i) providing a barrier to microorganisms; and
- (ii) providing a barrier to blood and bodily fluids;

said breathable film comprising at least five-layer film having as a minimum the following structure:

C:A:B:A:C;

where B comprises a microporous core layer containing at least one thermoplastic polymer and at least one particulate filler;

C comprises an outer monolithic layer

containing a hydrophilic polymeric resin capable of absorbing and desorbing moisture and providing a barrier to water and microorganisms, said C layer being substantially free of particulate filler; and,

A comprises a microporous adhesive layer for bonding said C layers to said core layer B, wherein said C layer substantially prevents the buildup of particulate filler material on a die during formation of said multilayer breathable film, and wherein said micropores are constructed and arranged to provide the passage of gaseous water but substantially prevent the passage of liquid water.

The invention also provides a novel method of making a stretched, multilayer breathable film having the combination of properties of:

- (i) providing a barrier to microorganisms; and
- (ii) providing a barrier to blood and bodily fluids;

said method comprising the steps of:

(a) simultaneously extruding at least a five-layer film from a die, said five-layer film having as a minimum the following structure:

C:A:B:A:C;

where B comprises a microporous core layer containing at least one thermoplastic polymer and at least one particulate filler;

C comprises an outer monolithic layer containing a hydrophilic polymeric

resin capable of absorbing and desorbing moisture and providing a barrier to aqueous fluids and microorganisms, said C layer being substantially free of particulate filler; and

A comprises a microporous adhesive layer for bonding said C layers to said core layer B, wherein said C layer substantially prevents the buildup of particulate filler material on said die during said extrusion step;

(b) stretching said extruded five-layer film to thereby form micropores in said microporous core layer and said microporous adhesive layer, wherein said stretching step is conducted and said microporous core layer and said microporous adhesive layers have been formulated so as to provide micropores which allow the passage of gaseous water but substantially prevent the passage of liquid water.

BRIEF DESCRIPTION OF THE DRAWINGS

Figure 1 illustrates a coextrusion flow plate which can be used in the present invention.

Figure 2 illustrates a stretching machine which can be used to stretch the multilayer material once it is extruded.

Figure 3 illustrates a standard cast embossed extrusion line which has been modified to extrude and stretch the multilayer breathable film in one step.

Figure 4 illustrates two options for orienting or stretching a multilayer film in a

continuous or sequential method.

DETAILED DESCRIPTION OF PREFERRED EMBODIMENTS

5

The invention provides a novel multilayer film having the following structure:

C:A:B:A:C,

where A comprises a microporous adhesive layer as described herein;

B comprises a microporous core layer as described herein; and

C comprises a monolithic layer as described herein.

Suitable thicknesses for each of the layers of the five-layer film have been found to be:

about 1 to about 40% by volume for each A layer;

about 1 to about 96% by volume for the B layer; and

about 1 to about 30% by volume for each C layer, the % volume being based on the volume of the five-layer film.

Preferably, each A layer is about 1 to about 10 % by volume; the B layer is about 60% to about 96% by volume; and each C layer is about 1 to about 10 % by volume.

More preferably, each A layer is about 1 to about 5 % by volume; the B layer is about 80% to about 96% by volume; and each C layer is about 1 to about 5 % by volume.

In an alternative embodiment, it is possible to make a three layer breathable film having the following structure:

C:D:C

Where each C layer comprises a monolithic layer as described herein; and

5 D is a microporous adhesive core layer. The adhesive core layer can contain the materials for making the adhesive layer A described herein. The five-layer film described above is preferred over the three layer film.

10 In the three layer film, the amount of D can vary from between about 2 to about 98% by volume and the amount of each C layer can vary from about 1 to about 49% by volume. Preferably, the amount of D can vary from between about 80 to about 98% by volume and the amount of each C layer can vary from about 1 to about 10% by volume. Most, preferably, the amount of D can vary from between about 90 to about 98% by volume and the amount of each C layer can vary from about 1 to about 5% by volume.

15 20 The multilayer films can be formed to any thickness for the desired application. Examples of suitable film thicknesses are between about .3 mils to about 20 mils, preferably about .5 mils to about 10 mils, and most preferably about .7 to about 3 mils.

25 30 Surprisingly, because the novel multilayer breathable films according to this invention contains two outer monolithic layers, the multilayer film can be made remarkably thin, on the order of about 1 mil or less, and yet still provide an effective barrier against microorganisms and bodily fluids.

Microporous Core Layer

5 The microporous core layer comprises at least a thermoplastic polymer and a particle filler for forming the micropores in the thermoplastic polymer during stretching. Any thermoplastic polymer, or mixtures thereof, which is suitable for forming a film can be used. Examples of suitable thermoplastic polymers are disclosed in U.S. patent Nos. 4,929,303 and 5,164,258, which are incorporated herein by reference.

10 Examples of suitable thermoplastic polymers are polyolefins, polyesters, and polyurethanes. The thermoplastic polymer can contain halogens, such as fluorine. Preferably, the thermoplastic polymer comprises a polyolefin. Specific examples of suitable polyolefins are polypropylene, copolymers of propylene, homopolymers and copolymers of ethylene and other alpha-olefins having from about 3 to about 20 carbon atoms. Linear low density polyethylene ("LLDPE") is particularly preferred.

15 Preferably, the thermoplastic polymer contains a metallocene catalyzed polyethylene such as the commercially available Exxon 3027 (Exxon). Other examples of suitable metallocene catalyzed polyethylene include:

25 The Exxon Exceed series, specifically: 350X60; 350X65; 357X80; 363X32; 377X60; 399X60; ECD-103; and ECD-202;

30 the Exxon Exact series, in particular: 3017; 3022; 3024; 3027; 3030; 3035; 3125; 3128; 3131; 3132; 4003; 4006; 4011; 4015; 4023; 4033; 4041; 4042; 4044; 4049; 4053; 4150; 4151; and 5008;

the Dow Engage series, in particular: 8003;

8100; 8150; 8180; 8200; 8300; 8400; 8401; 8402;
8403; 8411; 8440; 8441; 8445; 8450; 8452; 8480;
8490; 8499; 8500; 8540; 8550; and 8745;

the Dow Affinity series, in particular:

5 HF1030; HM1570; PL1840; PL1845; PL1880; PF1140;
FW1650; SM1300; GF1550; PT1450; PL1270; KC8852;
SM1350; PL12850; PL1881; SL1170; PT1409; SE1400;
and VP1770; and

the BASF Luflexan series, in particular:

10 0322HX; 0322LX; and 1712SX.

The particulate filler useful for making the
micropores in the film can be any inorganic or
organic material having a low affinity for and a
lower elasticity than the thermoplastic polymer
15 component. Preferably, the particulate filler is
a rigid material.

Specific examples of inorganic particulate
fillers include:

metal carbonates, such as,

barium carbonate;

calcium carbonate; and

magnesium carbonate;

metal hydroxides, such as,

aluminum hydroxide; and

25 magnesium hydroxide;

metal oxides, such as,

calcium oxide;

magnesium oxide;

titanium oxide;

30 titanium dioxide and

zinc oxide;

metal sulfates, such as,

barium sulfate;

calcium sulfate; and

magnesium sulfate;
clay;
kaolin;
talc;
5 silica;
diatomaceous earth;
alumina
mica
glass powder; and
10 zeolites. Calcium carbonate is preferred.

Commercial examples of suitable particulate filler concentrates include: Heritage HM-10 (Heritage Plastics); and, Ampacet LR-88250, 100720 and 100719 (Ampacet) These filler concentrates contain the filler, in this case calcium carbonate, at loadings from about 50 to about 75% by weight, and a thermoplastic carrier resin, in this case LLDPE, from about 50 to about 25% by weight.

The average size of the particulate filler should be large enough to form microvoids, but small enough to avoid forming holes or microvoids in adjacent layers during stretching, which are large enough to permit liquids to pass through the adjacent layer. Suitable average particle sizes are about .1 micron to about 10 microns, preferably, about .5 microns to about 5 microns, and more preferably about .8 microns to about 3 microns.

The particulate filler should be used in an amount which provides the desired amount of micropores. A suitable amount of particulate filler is about 30% to about 80% by weight of the layer, preferably, about 50 to about 70% by

weight.

The microporous core layer can contain scraps from any of the layers of the multilayer film. For example, the scraps can be mixed with the desired microporous core layer materials and then extruded. The amount of particulate filler present in the scraps should be taken into consideration when determining the amount of particulate filler to be added to the microporous core layer materials.

Outer Monolithic Layers

The outer monolithic layers comprise a hydrophilic polymeric resin. In this manner, water vapor contacting the outer monolithic layer can absorb into one side of the monolithic layer and then desorb out the other side of the monolithic layer. The monolithic layer can comprise any polymeric resin or combination of polymeric resins which is typically used to formulate moisture absorbent monolithic layers. Examples of suitable monolithic layer materials are disclosed in U.S. patent No. 5,164,258.

Specific examples of suitable hydrophilic polymeric resins include polyesters, polyamides, and grades of polyvinyl alcohol and ethyl vinyl alcohol which are substantially water insoluble at the ambient working temperature of the stretched film containing them.

Commercial examples of suitable hydrophilic polymeric resins include the Pebax series of resins sold by Elf Atochem, such as 3533, 4033, MV1074, MX1205, MV3000, MV1041, MV6200, X1892, and MH1657; the Hytrel series of resins sold by

DuPont, such as 8206, HTR8171, G4778; or Eastman 14766. Preferably the monolithic layer material comprises Hytrel 8206 or Pebax MV1074.

5 Preferably, the outer monolithic layers include a surface smoothing agent to improve the surface qualities of the film during extrusion. Commercial examples of such surface smoothing agents include the Viton® series of
10 fluoroelastomers from DuPont. To minimize agglomeration and gel formation, these fluoroelastomers should be let down in carrier resins which are similar or identical to the majority resin component in that layer. These
15 types of flow agents can be used in amounts up to about 10,000 ppm, preferably about 200 to about 2000 ppm, by weight of the materials present in the layer.

20 These free flow agents can also be used in the microporous core and microporous adhesive layers. Specific examples of suitable flow agents that can be used in the microporous layers include Ampacet LR-86769 (3% Viton A in 97% Hexene LLDPE) and Ampacet LR -88249 (3% Viton A in 97 % Octene LLDPE) which are manufactured by Ampacet.

25 Preferably, the selection of the monolithic material and the selection of the thickness of the outer monolithic layers is sufficient to provide an effective barrier to bodily fluids (including blood) and microorganisms. One skilled in the art
30 knows how to test the film barrier resistance to fluids and microorganisms. Based on the disclosure provided herein, one skilled in the art will be easily able to select a desired monolithic material and a desired thickness of the outer

monolithic layers. To minimize costs, the thickness of the outer monolithic layers should be as close as possible to the minimum thickness which will still provide an effective barrier to fluids and microorganisms.

Microporous Adhesive Layer

The adhesive layers can be made from any polymeric material which is capable of binding the monolithic layer to the microporous layer. The selection of the adhesive layer will depend on the type of the polymeric materials used for the monolithic and microporous layers. Based on the disclosure herein, one skilled in the art will easily be able to determine what polymeric materials will be suitable for bonding the monolithic layer to the microporous layer.

The adhesive layer which binds the outer monolithic layers to the core microporous layer must allow water vapor to pass therethrough. This can be accomplished by adding a particulate filler to the polymeric material used as the adhesive, whereby when the multilayer film is stretched the adhesive layer becomes microporous in the same manner as the microporous core layer.

Commercial examples of suitable polymeric materials for bonding the outer monolithic layers to the core layer include: Lotader 3210, 3420, and 3410 (Elf Atochem); Orevac 18302 and 18305 (Elf Atochem); Plexar PX5230, PX5298, and PX3342 (Quantum);

The adhesive layer can comprise a mixture of the polymers used in the core layer and the monolithic layers. Preferably, the adhesive layer

includes a mixture of recycled or scrap microporous and monolithic layer materials which are combined and extruded. More preferably, the adhesive layer can be made from recycled multilayer films. In this manner, the adhesive layer will already contain a filler material from the microporous core material. Additional, adhesive polymers can be added to optimize the performance of the adhesive layer.

By using scrap or recycled monolithic and microporous material layers as the adhesive, a significant efficiency is achieved. Furthermore, the multilayer film is more easily recycled.

The selection of the materials used for the microporous and monolithic layers will depend on the amount of stretching the multilayer film will be subject to. The stretching must be sufficient to make the thermoplastic polymer/filler mixture and the adhesive material microporous yet not too great that tears or holes in the monolithic layer are formed. One skilled in the art knows how to make a microporous layer, including what amount of stretching is required to provide micropores. Based on the disclosure provided herein, one skilled in the art would easily be able to determine what materials for the monolithic layer should be selected for the particular thermoplastic polymer/filler mixture and adhesive material utilized such that when the multilayer material is stretched, the core layer becomes microporous and the outer monolithic layers retain their integrity.

Formation of Micropores

The core and adhesive layers can be made microporous using industry standard stretching techniques. Preferably, the film is only stretched in the machine direction (hereinafter "monoaxially"). The machine direction is the direction the film is traveling when being formed.

Four factors determine the amount of porosity in the final stretched film:

- (1) the quantity, type and size of particulate filler particles;
- (2) the type of polymer present in the film layer;
- (3) the amount of volatiles present in the film material before extrusion; and
- (4) the draw ratio (amount of stretching).

In general, the greater the number of particulate filler particles, the greater the quantity of micropores that can be formed during stretching. The thermoplastic polymer material will form a micropore around most particulate filler particles.

Volatiles present in the material before extrusion can be released during extrusion of the film, to form micropores. Examples of typical volatiles are water and/or organic volatiles. If the quantity of volatiles is too great, the layer may foam or form large easily visible holes in the layer, which are undesirable. Therefore, the amount of volatiles are preferably reduced. Thermoplastic resins preferred for forming microporous films, in general, are very hydrophobic, and therefore a significant amount of water will not be present in the thermoplastic

starting materials. However, particulate fillers, such as calcium carbonate, in general are hydrophilic. For example, calcium carbonate concentrates contain about 800 to about 900 ppm of water, before drying. This amount of water is usually too great for use under normal extrusion conditions.

Another source of volatiles is the coating typically present on particulate fillers. For example stearic acid is typically used to coat calcium carbonate. The stearic acid may volatilize during the extrusion of the film, and thereby form microvoids. The amount of volatiles released from the organic coating on the particulate filler can be controlled by degassing the mineral during compounding.

The amount of water and/or organic volatiles present in the components before extruding the film should be an amount which is sufficiently low enough to prevent large holes or tears in the layer during the stretching step(s). The amount of water and/or organic volatiles present should be an amount which provides micropores having a diameter of about $\frac{1}{8}$ to about $\frac{1}{2}$ of the thickness of the stretched film. The desired amount of water and/or organic volatiles can be easily determined by adjusting the amount of water and/or organic volatiles present in the starting materials used to form the film until the desired size micropores are obtained. A suitable total volatile content for the particulate filler has been found to be between about 100 ppm and about 500 ppm, more preferably between about 100 ppm to about 300 ppm, based on the total weight of the

particulate filler. If there is too low a total volatile content, then there may be insufficient micropores formed from the volatilization in the film during extrusion to optimize the breathability of the stretched film..

The melt temperature of the film during extrusion will affect the amount of volatilization. In general, the higher the melt temperature, the greater the amount of volatilization formed during extrusion and the greater the amount of micropores formed.

Method of Making Multilayer Breathable Film

Based on the disclosure provided herein, conventional methods of making multilayer films can easily modified to practice the present invention. For example, the present invention can be practiced using a cast film extrusion method as well as a blown film extrusion method.

The method of making the multilayer breathable film will be described with reference to the drawings. The invention is not limited by the specific methods described in the drawings.

In the method according to the present invention, the multilayer film can be extruded and cooled, and then later heated and stretched to form a breathable multilayer film. Preferably, immediately after extrusion, the multilayer material is stretched before it is cooled (one step method). The extruded film can be stretched by any conventional method, including biaxially and monoaxially. Preferably, the extruded film is only stretched monoaxially in the direction the film is being extruded.

A preferred example of the multilayer film is a 5-layer film comprising a core microporous layer, two outer monolithic layers, and two adhesive layers which bind the outer layers to the core layer.

Two examples of suitable methods for stretching a multilayer material immediately upon extrusion in a one step method according to the present invention are shown in Figure 4.

As shown in Figure 4, in option 1, the 5-layer film shown at 10, is extruded from the die 1 and passes through a vacuum box 2 where it contacts a primary chill roll 3 and a nip plate out roll 4. The 5-layer material is stretched between the primary chill roll 3 and a secondary chill roll 5. The stretching area is shown as 6.

In option 2 shown in Figure 4, the polymer film 21 is extruded from the die 20 and passes through a vacuum box 30 where the film contacts the primary chill roll 25 and a nip plate out roll 26. The polymeric film is stretched between the primary chill roll 25 and the secondary chill roll 27. A nip roll 28 keeps film material against second chill roll 27. The stretching area is shown at 29. While polymeric film 21 is contacting the primary chill roll 25, a rubber roll or silicone roll 24 which is coated with water contacts the film 21 to aid in the cooling and release of the film off the primary chill roll 25. Water is provided on the rubber roll 24 by water present in the pan 23. The rubber roll 24 is cleaned using wiper roll 22.

The stretching can be done in more than one step, for example, in two, three, four, or more

steps.

The invention also relates to a multilayer film comprising the two outer monolithic layers described herein, the core microporous layer described herein, and the adhesive layers described herein which bind the outer monolithic layers to the core microporous layer.

The multilayer breathable film is suitable for but not limited to use in making surgical gowns, bandages, hospital bed pads, disposable diapers, house wrap, feminine napkins, protective clothing, shoe liners, food packaging, and gloves.

The invention will be further explained by the following non-limiting examples.

Example 1

Three different resin compositions in the form of unmelted solid pellets were charged into three different extruders, extruder A, extruder B, and extruder C. The particular resin composition that went into each extruder is shown in the following Table I.

TABLE 1

RESIN BLEND					
Extruder "B"	WT %	EXTRUDER "A"	WT %	EXTRUDER "C"	WT %
Heritage HM-10	70 %	Hytrel G4778	33 %	Hytrel G4778	100 %
Exxon 3027	30 %	Heritage HM-10	47 %		
		Exxon 3027	20 %		
Thickness "B" (%)	40	Thickness* "A" (%)	20/20	Thickness* "C" (%)	10/10

- Because the "A" and "C" materials are each two layers, the thicknesses listed are the thickness for each layer as a percentage based on the total thickness of the multilayer film produced.

Heritage HM-10 is 75% calcium carbonate and 25% linear low density polyethylene.

Exxon 3027 is metallocene polyethylene.

Hytrel G4778 (DuPont) is a monolithic, elastomeric polyester.

Thus, the "A" layer is the adhesive layer, the "B" layer is the microporous layer, and the "C" layer is the monolithic layer.

The extruders converted the unmelted solid into a liquid state using heat and work. A crammer using an auger loaded the resins into the hopper portion of extruders. The resins were forced through the extruder using a screw. The barrel area of the extruder was divided into regions or zones. Each zone was heated so that the resin was further melted as it passed through the extruder.

The molten resins passed through a screen pack area. Each pack area had a temperature zone.

The purpose of the screen pack was to filter out all unmolten materials which may have passed through the extruder such as cardboard, dirt,

carbon, etc. The greater the density of the molten resins, the thinner the mesh and greater the head pressure and melt temperature that was used.

5 From the extruder screws, the molten resins traveled through connecting pipes into an extrusion block. The extrusion block rested on top of the die. The extrusion block is where all of the connecting pipes met and the melt streams were combined in the die via a coextrusion block which is most often referred to as a flow plate. The particular flow plate used is shown in Figure 1. As shown in Fig. 1, the three molten resins from the connecting pipes passed into three separate holes labeled A, B and C. The molten resins then came out of the five holes on the bottom side of the flow plate as a C:A:B:A:C extrusion with the following percentage volumes: 10/20/40/20/10. The die used had seven heat
15 zones. The heats on the die can be adjusted to vary the gauge.

20 A 5-layer unstretched film was extruded using this method. After being extruded, the 5-layer unstretched film was annealed by passing over the heated rolls shown in Fig. 3. Fig. 3 also shows
25 how the extrusion line can be modified using

options 1 or 2, described above, to extrude and stretch the multilayer film in one step.

The unstretched film was then taken to a separate machine shown in Fig. 2 for stretching.

5 As shown in Fig. 2, a roll of the unstretched film, shown at 30, was unwound and entered the MDO (Machine Direction and Orientation) process shown at 40. The film in the MDO process 40 was first preheated by passing over two rolls labeled 41 and 42. The film then traveled between roll 43 and a nip, and roll 44 and a nip. The stretching took place between the rolls 43 and 44. Roll 43 was moving slower than roll 44. The ratio of the speeds of the two rolls is known as the draw ratio. The greater the distance between rolls 43 and 44, the greater amount of neck-in which will be seen. Neck-in is the amount of reduction in the width of the film when it is stretched.

After stretching, the film was annealed.

20 Roll 45 is where the annealing process starts to take place. In general, annealing is the way in which dimensional stability is achieved after the stretching process. Annealing was accomplished by first heating the film by passing it over roll 45 and then cooling the film by passing it over roll 25 46. Together, the heating and cooling causes the

stresses in the film to be removed and equilibrium reached. During annealing, an embossing pattern can be applied to the film by compressing the film under high pressure onto an annealing roll which has been engraved with the desired pattern.

The film was then slit, shown at 50, and wound into a final product, shown at 60. A trial run of the material were stretched using the parameters shown in Table 2.

TABLE 2

Trial 1

Preheat Temperature
(Rolls 41 and 42):

139

Slow Draw
(Roll 43):

Temperature:
Speed:
Amps:

151
23.2
3.9

Fast Draw
(Roll 44):

Temperature:
Speed:
Amps:

144
58.2
1

Heat Set
(Roll 45):

Temperature:
Speed:
Amps:

162
58.6
1.9

Cooling
(Roll 46):

Temperature:
Speed:
Amps:

64
60.6
2.3

Material Characteristics at Inlet:

Width 28
Thickness 3.5.mil

Material Characteristics at Exit:

Width 25

Draw Ratio:

2.5:1

*Nips were always closed and the draw
roll gap was always kept to a minimum

The neck-in is the difference between the widths
of the multilayer material at the inlet and the
exit.

The unstretched multilayer material was translucent. However, once stretched, the material took on an opaque white sheen. Because the material had two outer monolithic layers free of filler material, no buildup of the filler was seen on the extrusion die.

Because the material has two outer monolithic layers, the material provides an effective barrier against microorganisms.

Example 2

Example 1 was repeated except using the materials shown in Table 3. The parameters used for stretching the extruded films are shown in Table 4.

TABLE 3

ETRUDER "B"	WT %	EXTRUDER "A"	WT %	EXTRUDER "C"	WT %
Heritage HM-10	70%	Pebax X1892	33%	Pebax X1892	100%
Exxon 3027	30%	Heritage HM-10	47%		
		Exxon 3027	20%		
Thickness "B" (%)	40	Thickness "A" (%)	20/20	Thickness "C" (%)	10/10

TABLE 4

	<u>Trial 2</u>	<u>Trial 3</u>	<u>Trial 4</u>
Preheat Temperature (Rolls 41 and 42):	141	141	140
Slow Draw (Roll 43):			
Temperature:	149	149	150
Speed:	38	38	38
Amps:	4	3.9	4
Fast Draw (Roll 44):			
Temperature:	146	145	145
Speed:	115.5	134.8	135.0
Amps:	1.2	1.2	1.2
Heat Set (Roll 45):			
Temperature:	201	201	200
Speed:	115.7	135	135
Amps:	2.3	2.5	2.5
Cooling (Roll 46):			
Temperature:	67	67	67
Speed:	115.8	135.5	135.8
Amps:	1.75	1.9	1.9
Material Characteristics at Inlet:			
Width	28	28	28
Thickness	3 mil	3 mil	3.5 mil
Material Characteristics at Exit:			
Width	23.75	23.5	24
Draw Ratio:	3.0:1	3.5:1	3.5:1

*Nips were always closed and the draw roll gap was always kept to a minimum.

The neck-in is the difference between the widths of the multilayer material at the inlet and the exit.

TRIAL 1

PROPERTY	ASTM TEST #	UNITS	
GAUGE	D 2103	mils	1.97
YIELD	---	in ² /lb	14,030
LIGHT TRANSMISSION	D 1003	%	39.1
GLOSS - (A SIDE)	D 2457	%	24.0
GLOSS - (B SIDE)	D 2457	%	19.7
DART DROP	D1709	grams	278
*STATIC MVTR @ 100°F 50% Hum.	E96B	g/m ² /24hr	143
*STATIC MVTR @ 100°F 50% Hum.	E96BW	g/m ² /24hr	115
MOCON MVTR @ 100°F 100% Hum.	---	g/m ² /24hr	176
M.D. STRIP GAUGE	D 2103	mils	1.97
M.D. TENSILE @ BREAK	D 882	grams	4,632
M.D. ELONGATION	D 882	%	194
M.D. TENSILE @ YIELD	D 882	grams	1,325
M.D. ELOGATION @ YIELD	D 882	%	5.67
M.D. TENSILE @ 5%	D 882	grams	622
M.D. TENSILE @ 10%	D 882	grams	1,204
M.D. TENSILE @ 25%	D 882	grams	2,369
MD SECANT MODULUS	D882	p.s.i.	14,055
T.D. STRIP GAUGE	D 2103	mils	1.98
T.D. TENSILE @ BREAK	D 882	grams	1,075
T.D. ELONGATION	D 882	%	514
T.D. TENSILE @ YIELD	D 882	grams	1,230
T.D. ELOGATION @ YIELD	D 882	%	4.86
T.D. TENSILE @ 5%	D 882	grams	388
T.D. TENSILE @ 10%	D 882	grams	494
T.D. TENSILE @ 25%	D 882	grams	560
T.D. SECANT MODULUS	D882	p.s.i.	15,106
C.O.F. - (A/A)	D 1894	-----	2.72
C.O.F. - (B/B)	D 1894	-----	2.98

*Modified ASTM procedure: no air circulation above
the sample

TRIAL 2

PROPERTY	ASTM TEST #	UNITS	
GAUGE	D 2103	mils	1.26
YIELD	---	in ² /lb	22,430
LIGHT TRANSMISSION	D 1003	%	30.3
GLOSS - (A SIDE)	D 2457	%	26.3
GLOSS - (B SIDE)	D 2457	%	20.9
DART DROP	D1709	grams	238
*STATIC MVTR @ 100°F 50% Hum.	E96B	g/m ² /24hr	230
M.D. STRIP GAUGE	D 2103	mils	1.26
M.D. TENSILE @ BREAK	D 882	grams	4,662
M.D. ELONGATION	D 882	%	75
M.D. TENSILE @ YIELD	D 882	grams	1,325
M.D. ELOGATION @ YIELD	D 882	%	5.67
M.D. TENSILE @ 5%	D 882	grams	886
M.D. TENSILE @ 10%	D 882	grams	1,759
M.D. TENSILE @ 25%	D 882	grams	2,950
M D SECANT MODULUS	D882	psi	27,033
T.D. STRIP GAUGE	D 2103	mils	1.25
T.D. TENSILE @ BREAK	D 882	grams	710
T.D. ELONGATION	D 882	%	453
T.D. TENSILE @ YIELD	D 882	grams	1,230
T.D. ELOGATION @ YIELD	D 882	%	4.86
T.D. TENSILE @ 5%	D 882	grams	484
T.D. TENSILE @ 10%	D 882	grams	419
T.D. TENSILE @ 25%	D 882	grams	479
T.D. SECANT MODULUS	D882	p.s.i.	25,536
C.O.F. - (A/A)	D 1894	-----	2.59
C.O.F. - (B/B)	D 1894	-----	1.31

*Modified ASTM procedure: no air circulation above the sample.

TRIAL 3

PROPERTY	ASTM TEST #	UNITS	
GAUGE	D 2103	mils	1.13
YIELD	---	in ² /lb	24,021
LIGHT TRANSMISSION	D 1003	%	28.9
GLOSS - (A SIDE)	D 2457	%	25.4
GLOSS - (B SIDE)	D 2457	%	19.7
DART DROP	D1709	grams	238
*STATIC MVTR @ 100°F 50% Hum.	E96B	g/m ² /24hr	257
*STATIC MVTR @ 100°F 50% Hum.	E96BW	g/m ² /24hr	230
MOCON MVTR @ 100°F 100% Hum.	---	g/m ² /24hr	380
M.D. STRIP GAUGE	D 2103	mils	1.15
M.D. TENSILE @ BREAK	D 882	grams	5,505
M.D. ELONGATION	D 882	%	66
M.D. TENSILE @ YIELD	D 882	grams	1,325
M.D. ELOGATION @ YIELD	D 882	%	5.67
M.D. TENSILE @ 5%	D 882	grams	936
M.D. TENSILE @ 10%	D 882	grams	1,853
M.D. TENSILE @ 25%	D 882	grams	3,450
M D SECANT MODULUS	D882	p.s.i.	30,491
T.D. STRIP GAUGE	D 2103	mils	1.12
T.D. TENSILE @ BREAK	D 882	grams	656
T.D. ELONGATION	D 882	%	473
T.D. TENSILE @ YIELD	D 882	grams	1,230
T.D. ELOGATION @ YIELD	D 882	%	4.86
T.D. TENSILE @ 5%	D 882	grams	357
T.D. TENSILE @ 10%	D 882	grams	414
T.D. TENSILE @ 25%	D 882	grams	412
T.D. SECANT MODULUS	D882	p.s.i.	24,731
C.O.F. - (A/A)	D 1894	-----	3.38
C.O.F. - (B/B)	D 1894	-----	1.54

*Modified ASTM procedure: no air circulation
above the sample

TRIAL 4

PROPERTY	ASTM TEST #	UNITS	
GAUGE	D 2103	mils	1.38
YIELD	---	IN ² /lb	18,343
LIGHT TRANSMISSION	D 1003	%	32.0
GLOSS - (A SIDE)	D 2457	%	25.0
GLOSS - (B SIDE)	D 2457	%	20.7
DART DROP	D1709	grams	418
*STATIC MVTR @ 100°F50% Hum.	E96B	g/m2/24hr	186
M.D. STRIP GAUGE	D 2103	mils	1.36
M.D. TENSILE @ BREAK	D 882	grams	6,314
M.D. ELONGATION	D 882	%	111
M.D. TENSILE @ YIELD	D 882	grams	1,325
M.D. ELOGATION @ YIELD	D 882	%	5.67
M.D. TENSILE @ 5%	D 882	grams	935
M.D. TENSILE @ 10%	D 882	grams	1,847
M.D. TENSILE @ 25%	D 882	grams	3,120
MD SECANT MODULUS	D882	p.s.i.	29,077
T.D. STRIP GAUGE	D 2103	mils	1.35
T.D. TENSILE @ BREAK	D 882	grams	1,046
T.D. ELONGATION	D 882	%	509
T.D. TENSILE @ YIELD	D 882	grams	1,230
T.D. ELOGATION @ YIELD	D 882	%	4.86
T.D. TENSILE @ 5%	D 882	grams	610
T.D. TENSILE @ 10%	D 882	grams	526
T.D. TENSILE @ 25%	D 882	grams	601
T.D. SECANT MODULUS	D882	p.s.i.	28,347
C.O.F. - (A/A)	D 1894	-----	1.63
C.O.F. - (B/B)	D 1894	-----	.86

*Modified ASTM procedure: no air circulation
above the sample.

The results in the Tables labeled Trial 1-4, demonstrate that the multilayer films produced according to this invention exhibit a good moisture vapor transmission rate. All of the films exhibited a moisture vapor transmission rate of 115 to 380 g/m²/24hr.

The films also exhibited good mechanical characteristics. The tensile strength, elongation, and modulus were sufficiently high such that the material can be used as a component of a reinforced surgical gown. In particular, the tensile strength, elongation, and modulus were significantly higher than those of conventional materials, such as polyethylene, which are used for surgical gowns.

The films exhibited a high puncture resistance as measured by the dart drop test. A high puncture resistance is desirable because during a surgery, if the material is punctured, microorganisms would be able to penetrate the material and infect the medical personnel.

The light transmission test demonstrates that the films blocked more than about 60% of the light, which is desirable to hide the individual or object covered by the film material.

The films exhibited a secant modulus in a range which provides adequate softness, drapability and comfort.

5 A biological penetration test was performed by TRI/Environmental, Inc., on one sample film made according to Example 1 and one sample film made according to Example 2, using ASTM ES21 and ASTM ES22. Three samples of each sample film were tested. All of the samples passed both ASTM methods after flexing. The ES21 test is a synthetic blood penetration test. The ES22 test is a live microorganism penetration test. Because the film material passed both tests, the film material can be used for surgical gowns.

Example 3-7

Example 1 was repeated except using the materials shown in Tables 5-9. The parameters used for stretching the extruded films are shown in Table 10.

Table 5
Example 3

EXTRUDER "B"	WT. %	EXTRUDER "A"	WT. %	EXTRUDER "C"	WT. %
Ampacet 100720	80	Ampacet 100720	80	Pebax MV3000	100
Exxon 357C80	20	Exxon 357C80	10		
		Pebax MV3000	10		
Thickness "B" (%)	60.9	Thickness "A" (%)	17 / 17	Thickness "C" (%)	0.8 / 0.8

Table 6
Example 4

EXTRUDER "B"	WT. %	EXTRUDER "A"	WT. %	EXTRUDER "C"	WT. %
Heritage HM-10	70	Ampacet 100719	75	Pebax MV1074	100
Exxon 357C80	30	Lotader 3410	25		
Thickness "B" (%)	64.4	Thickness "A" (%)	14.45 / 14.45	Thickness "C" (%)	3.35 / 3.35

Table 7
Example 5

EXTRUDER "B"	WT. %	EXTRUDER "A"	WT. %	EXTRUDER "C"	WT. %
Heritage HM-10	70	Ampacet 100719	75	Pebax MV1074	100
Exxon 357C80	30	Lotader 3410	25		
Thickness "B" (%)	62.9	Thickness "A" (%)	15.15 / 15.15	Thickness "C" (%)	3.45 / 3.45

TABLE 8
Example 6

EXTRUDER "B"	WT. %	EXTRUDER "A"	WT. %	EXTRUDER "C"	WT. %
Ampacet 100720	80	Ampacet 100720	75	Ampacet 100720	60
Exxon 357C80	20	Exxon 357C80	23	Exxon 357C80	37
		Ampacet LR-88162	2	Ampacet LR-86769	3
Thickness "B" (%)	63	Thickness "A" (%)	16.5/ 16.5	Thickness "C" (%)	2/2

Table 9
Example 7

EXTRUDER "B"	WT. %	EXTRUDER "A"	WT. %	EXTRUDER "C"	WT. %
Ampacet 100720	80	Ampacet 100720	75	Ampacet 100720	60
Exxon 363C80	20	Exxon 363C80	23	Exxon 363C80	37
		Ampacet LR-88162	2	Ampacet LR-86769	3
Thickness "B" (%)	63	Thickness "A" (%)	16.5/ 16.5	Thickness "C" (%)	2/2

Table 10

Preheat Temperature:

Slow Draw:

Temperature
Speed:
Amps:

Fast Draw:

Temperature
Speed:
Amps:

Heat Set:

Temperature
Speed:
Amps:

Cooling: Temperature:
Speed:

Amps:

Material Characteristic at Inlet:

Width
Thickness

Material Characteristic at Exit:

Width

Draw Ratio:

	Ex 4	Ex 5	Ex 5	Ex 3	Ex 6	Ex 7
	83	83	83	85	82	82
Temperature	155	156	156	157	155	155
Speed:	33.4	35	35.1	32.2	35	32.2
Amps:	4	4.1	4	4	4	4
Temperature	169	170	170	170	170	170
Speed:	120.3	124.6	131.2	119.5	174	132.6
Amps:	1	1	1.1	1	1	1.5
Temperature	164	164	164	165	164	164
Speed:	120.6	124.8	131.4	119.7	174.2	132.8
Amps:	2.1	2.1	2.1	2.5	2	2.5
Temperature	63	63	63	63	63	64
Speed:	121.7	125.9	132.4	120.9	174.6	133.1
Amps:	1.2	1.1	1.2	1.2	1.5	1.2
Material Characteristic at Inlet:						
Width	28 1/8	28	28	28	28	28
Thickness	1.5	2.25	2.25	2.25	2.2	2.25
Material Characteristic at Exit:						
Width	25.5	25.5	25.75	24 7/8	24.5	24 7/8
Draw Ratio:	4.0:1	4.0:1	4.25:1	4.5:1	5.0:1	5.0:1

The unstretched multilayer materials of examples 3-5 were translucent. However, once stretched, the materials took on an opaque white sheen. Because the materials had two outer monolithic layers free of filler material, no buildup of the filler was seen on the extrusion die. Because the materials of examples 3-5 had two outer monolithic layers, the materials provides an effective barrier against microorganisms.

Having two outer monolithic layers separated by a microporous layer provides the added safety that penetration must be made through all three layers before microorganisms can pass therethrough. In contrast, in multilayer materials which have only one core monolithic layer, penetration must only be made through two layers to provide passage of microorganisms which can pass through microporous films.

The properties of the multilayer films (unstretched and stretched) produced in Examples 3-7 were measured. The results are shown in the following Tables.

Example 3 (unstretched)

PROPERTY	ASTM TEST #	UNITS	
GAUGE	D 2103	mils	1.60
LIGHT TRANSMISSION	D 1003	%	74.4
GLOSS - (STEEL ROLL / OUT)	D 2457	%	5.3
GLOSS - (AIR SIDE / IN)	D 2457	%	5.1
M.D. STRIP GAUGE	D 2103	mils	1.66
M.D. TENSILE @ BREAK	D 882	grams	2,022
M.D. ELONGATION	D 882	%	544
M.D. TENSILE @ YIELD	D 882	grams	982
M.D. ELOGATION @ YIELD	D 882	%	8.90
M.D. TENSILE @ 5%	D 882	grams	926
M.D. TENSILE @ 10%	D 882	grams	979
M.D. TENSILE @ 25%	D 882	grams	902
T.D. STRIP GAUGE	D 2103	mils	1.63
T.D. TENSILE @ BREAK	D 882	grams	1,317
T.D. ELONGATION	D 882	%	543
T.D. TENSILE @ YIELD	D 882	grams	880
T.D. ELOGATION @ YIELD	D 882	%	7.90
T.D. TENSILE @ 5%	D 882	grams	842
T.D. TENSILE @ 10%	D 882	grams	871
T.D. TENSILE @ 25%	D 882	grams	797
C.O.F. - (IN / IN)	D 1894	-----	1.25
C.O.F. - (OUT / OUT)	D 1894	-----	1.28

Example 3 (stretched)

PROPERTY	ASTM TEST #	UNITS	4.5 : 1	4.75 : 1	4.95 : 1
YIELD	-----	in ² /lb	41,299	43,765	40,956
GAUGE	D 2103	mils	0.69	0.63	0.71
LIGHT TRANSMISSION	D 1003	%	33.2	33.8	30.9
GLOSS - (A SIDE)	D 2457	%	10.9	11.4	12.0
GLOSS - (B SIDE)	D 2457	%	10.5	10.6	12.2
DART DROP	D 1709	grams	95	72	78
MVTR (UPRIGHT / INVERTED)	E 96B/E96BW	g/m ² /day	3,285 / 4,061	3,444 / 4,062	3,410 / 4,077
M.D. STRIP GAUGE	D 2103	mils	0.70	0.62	0.70
M.D. TENSILE @ BREAK	D 882	grams	1,955	1,979	2,069
M.D. ELONGATION	D 882	%	58	53	48
M.D. TENSILE @ 5%	D 882	grams	306	287	347
M.D. TENSILE @ 10%	D 882	grams	569	549	647
M.D. TENSILE @ 25%	D 882	grams	1,209	1,231	1,463
M.D. SECANT MODULUS	D 882	p.s.i	23,120	24,520	24,690
T.D. STRIP GAUGE	D 2103	mils	0.69	0.62	0.71
T.D. TENSILE @ BREAK	D 882	grams	206	192	189
T.D. ELONGATION	D 882	%	369	318	309
T.D. TENSILE @ 5%	D 882	grams	78	74	69
T.D. TENSILE @ 10%	D 882	grams	117	113	109
T.D. TENSILE @ 25%	D 882	grams	151	147	148
T.D. ELOGATION @ YIELD	D 882	%	38	34	31
T.D. TENSILE @ YIELD	D 882	grams	155	151	151
T.D. SECANT MODULUS	D 882	p.s.i.	8,880	9,049	7,888
C.O.F. - (A / A)	D 1894	-----	0.86	0.86	0.86
C.O.F. - (B / B)	D 1894	-----	0.78	0.79	0.83

In examples 3-9, the ASTM tests E96B and E96BW were all run at 100°F to emulate the temperature of the Human Body. Furthermore, ASTM E96BW was run without circulation of air.

Example 4 (unstretched)

PROPERTY	ASTM TEST #	UNITS	
GAUGE	D 2103	mils	1.25
LIGHT TRANSMISSION	D 1003	%	79.1
GLOSS - (STEEL ROLL / OUT)	D 2457	%	4.8
GLOSS - (AIR SIDE / IN)	D 2457	%	4.9
M.D. STRIP GAUGE	D 2103	mils	1.25
M.D. TENSILE @ BREAK	D 882	grams	1,544
M.D. ELONGATION	D 882	%	474
M.D. TENSILE @ YIELD	D 882	grams	*****
M.D. ELOGATION @ YIELD	D 882	%	*****
M.D. TENSILE @ 5%	D 882	grams	747
M.D. TENSILE @ 10%	D 882	grams	780
M.D. TENSILE @ 25%	D 882	grams	803
T.D. STRIP GAUGE	D 2103	mils	1.21
T.D. TENSILE @ BREAK	D 882	grams	1,146
T.D. ELONGATION	D 882	%	541
T.D. TENSILE @ YIELD	D 882	grams	683
T.D. ELOGATION @ YIELD	D 882	%	5.21
T.D. TENSILE @ 5%	D 882	grams	682
T.D. TENSILE @ 10%	D 882	grams	668
T.D. TENSILE @ 25%	D 882	grams	650
C.O.F. - (IN / IN)	D 1894	-----	1.19
C.O.F. - (OUT / OUT)	D 1894	-----	1.26

Example 4 (stretched)

PROPERTY	ASTM TEST #	UNITS	4.0 : 1	4.1 : 1	4.25 : 1
YIELD	-----	in ² /lb	54135	570825	610272
GAUGE	D 2103	mils	.52	0.49	0.48
LIGHT TRANSMISSION	D 1003	%	42.8	42.7	42.2
GLOSS - (A SIDE)	D 2457	%	10.5	10.6	10.8
GLOSS - (B SIDE)	D 2457	%	10.5	10.7	11.2
DART DROP	D 1709	grams	<30	<30	<30
MVTR (UPRIGHT / INVERTED)	E 96B/E96BW	g/m ² /day	1,032 / 750	2,146 / 1,411	2,578 / 2,337
M.D. STRIP GAUGE	D 2103	mils	0.52	0.52	0.49
M.D. TENSILE @ BREAK	D 882	grams	1,528	1,410	1,553
M.D. ELONGATION	D 882	%	49	47	43
M.D. TENSILE @ 5%	D 882	grams	306	282	314
M.D. TENSILE @ 10%	D 882	grams	582	534	600
M.D. TENSILE @ 25%	D 882	grams	1,262	1,165	1,332
M.D. SECANT MODULUS	D 882	p.s.i	19,088	29,840	31,780
T.D. STRIP GAUGE	D 2103	mils	0.54	0.48	0.50
T.D. TENSILE @ BREAK	D 882	grams	148	152	134
T.D. ELONGATION	D 882	%	97	132	47
T.D. TENSILE @ 5%	D 882	grams	96	88	83
T.D. TENSILE @ 10%	D 882	grams	129	129	118
T.D. TENSILE @ 25%	D 882	grams	143	145	134
T.D. ELOGATION @ YIELD	D 882	%	21	19	18
T.D. TENSILE @ YIELD	D 882	grams	143	144	133
T.D. SECANT MODULUS	D 882	p.s.i.	10,138	15,357	11,400
C.O.F. - (A / A)	D 1894	-----	0.55	0.46	0.95
C.O.F. - (B / B)	D 1894	-----	0.54	0.46	0.90

Example 5 (unstretched)

PROPERTY	ASTM TEST #	UNITS	
GAUGE	D 2103	mils	2.0
LIGHT TRANSMISSION	D 1003	%	72.7
GLOSS - (STEEL ROLL / OUT)	D 2457	%	6.0
GLOSS - (AIR SIDE / IN)	D 2457	%	6.3
M.D. STRIP GAUGE	D 2103	mils	1.96
M.D. TENSILE @ BREAK	D 882	grams	2,341
M.D. ELONGATION	D 882	%	515
M.D. TENSILE @ YIELD	D 882	grams	1,220
M.D. ELONGATION @ YIELD	D 882	%	29.50
M.D. TENSILE @ 5%	D 882	grams	1,192
M.D. TENSILE @ 10%	D 882	grams	1,218
M.D. TENSILE @ 25%	D 882	grams	1,225
T.D. STRIP GAUGE	D 2103	mils	1.90
T.D. TENSILE @ BREAK	D 882	grams	1,849
T.D. ELONGATION	D 882	%	551
T.D. TENSILE @ YIELD	D 882	grams	1,104
T.D. ELONGATION @ YIELD	D 882	%	5.21
T.D. TENSILE @ 5%	D 882	grams	1,101
T.D. TENSILE @ 10%	D 882	grams	1,081
T.D. TENSILE @ 25%	D 882	grams	1,045
C.O.F. - (IN / IN)	D 1894	-----	1.34
C.O.F. - (OUT / OUT)	D 1894	-----	1.29

Example 5 (stretched)

PROPERTY	ASTM TEST #	UNITS	4.0 : 1	4.25 : 1	4.5 : 1
YIELD	-----	in ² /lb	35,113	37,024	40,905
GAUGE	D 2103	mils	0.83	0.75	0.69
LIGHT TRANSMISSION	D 1003	%	33.1	33.4	32.9
GLOSS - (A SIDE)	D 2457	%	11	11.7	11
GLOSS - (B SIDE)	D 2457	%	11.6	10.8	12.4
DART DROP	D 1709	grams	85	71	71
MVTR (UPRIGHT / INVERTED)	E 96B/E96BW	g/m ² /day	330 / 270	488 / 304	517 / 485
M.D. STRIP GAUGE	D 2103	mils	0.82	0.67	0.69
M.D. TENSILE @ BREAK	D 882	grams	2,470	2,370	2,433
M.D. ELONGATION	D 882	%	81	50	37
M.D. TENSILE @ 5%	D 882	grams	436	434	468
M.D. TENSILE @ 10%	D 882	grams	800	824	882
M.D. TENSILE @ 25%	D 882	grams	1,619	1,840	2,055
M.D. SECANT MODULUS	D 882	p.s.i	28,583	15,603	33,770
T.D. STRIP GAUGE	D 2103	mils	0.82	0.73	0.69
T.D. TENSILE @ BREAK	D 882	grams	283	225	187
T.D. ELONGATION	D 882	%	309	281	194
T.D. TENSILE @ 5%	D 882	grams	176	132	116
T.D. TENSILE @ 10%	D 882	grams	224	181	161
T.D. TENSILE @ 25%	D 882	grams	241	196	180
T.D. ELOGATION @ YIELD	D 882	%	24	19	18
T.D. TENSILE @ YIELD	D 882	grams	241	198	179
T.D. SECANT MODULUS	D 882	p.s.i.	17,750	17,247	15,577
C.O.F. - (A / A)	D 1894	-----	0.94	0.95	0.93
C.O.F. - (B / B)	D 1894	-----	0.92	0.97	0.91

Example 6 (unstretched)

PROPERTY	ASTM TEST #	UNITS	
GAUGE	D 2103	mils	2.25
LIGHT TRANSMISSION	D 1003	%	57.9
GLOSS - (STEEL ROLL / OUT)	D 2457	%	5.5
GLOSS - (AIR SIDE / IN)	D 2457	%	5.5
M.D. STRIP GAUGE	D 2103	mils	2.26
M.D. TENSILE @ BREAK	D 882	grams	2,867
M.D. ELONGATION	D 882	%	569
M.D. TENSILE @ YIELD	D 882	grams	1,325
M.D. ELOGATION @ YIELD	D 882	%	5.67
M.D. TENSILE @ 5%	D 882	grams	1,319
M.D. TENSILE @ 10%	D 882	grams	1,228
M.D. TENSILE @ 25%	D 882	grams	1,132
T.D. STRIP GAUGE	D 2103	mils	2.26
T.D. TENSILE @ BREAK	D 882	grams	2,071
T.D. ELONGATION	D 882	%	563
T.D. TENSILE @ YIELD	D 882	grams	1,230
T.D. ELOGATION @ YIELD	D 882	%	4.86
T.D. TENSILE @ 5%	D 882	grams	1,227
T.D. TENSILE @ 10%	D 882	grams	1,093
T.D. TENSILE @ 25%	D 882	grams	1,041
C.O.F. - (IN / IN)	D 1894	-----	.48
C.O.F. - (OUT / OUT)	D 1894	-----	.46

Example 6 (stretched)

PROPERTY	ASTM TEST #	UNITS	5.0 : 1	5.25 : 1
YIELD	-----	in ² /lb	38,849	39,591
GAUGE	D 2103	mils	0.84	0.87
LIGHT TRANSMISSION	D 1003	%	22.5	21.1
GLOSS - (A SIDE)	D 2457	%	10.9	9.8
GLOSS - (B SIDE)	D 2457	%	9.6	12.0
DART DROP	D 1709	grams	100	72
MVTR (UPRIGHT / INVERTED)	E 96B/E96BW	g/m ² /day	3,727 / 4,013	3,829 / 4,018
M.D. STRIP GAUGE	D 2103	mils	0.83	0.85
M.D. TENSILE @ BREAK	D 882	grams	2,483	2,530
M.D. ELONGATION	D 882	%	34	27
M.D. TENSILE @ 5%	D 882	grams	513	585
M.D. TENSILE @ 10%	D 882	grams	1,006	1,135
M.D. TENSILE @ 25%	D 882	grams	2,250	2,220
M.D. SECANT MODULUS	D 882	p.s.i	29,010	32,300
T.D. STRIP GAUGE	D 2103	mils	0.81	0.81
T.D. TENSILE @ BREAK	D 882	grams	226	209
T.D. ELONGATION	D 882	%	398	381
T.D. TENSILE @ 5%	D 882	grams	74	67
T.D. TENSILE @ 10%	D 882	grams	122	110
T.D. TENSILE @ 25%	D 882	grams	164	158
T.D. ELOGATION @ YIELD	D 882	%	26	27
T.D. TENSILE @ YIELD	D 882	grams	164	159
T.D. SECANT MODULUS	D 882	p.s.i.	7,032	7,500
C.O.F. - (A / A)	D 1894	-----	0.40	0.39
C.O.F. - (B / B)	D 1894	-----	0.43	0.42

Example 7 (unstretched)

PROPERTY	ASTM TEST #	UNITS	
GAUGE	D 2103	mils	2.25
LIGHT TRANSMISSION	D 1003	%	59.4
GLOSS - (STEEL ROLL / OUT)	D 2457	%	5.7
GLOSS - (AIR SIDE / IN)	D 2457	%	5.5
M.D. STRIP GAUGE	D 2103	mils	2.30
M.D. TENSILE @ BREAK	D 882	grams	3,068
M.D. ELONGATION	D 882	%	563
M.D. TENSILE @ YIELD	D 882	grams	1,348
M.D. ELOGATION @ YIELD	D 882	%	5.75
M.D. TENSILE @ 5%	D 882	grams	1,340
M.D. TENSILE @ 10%	D 882	grams	1,267
M.D. TENSILE @ 25%	D 882	grams	1,166
T.D. STRIP GAUGE	D 2103	mils	2.30
T.D. TENSILE @ BREAK	D 882	grams	2,258
T.D. ELONGATION	D 882	%	569
T.D. TENSILE @ YIELD	D 882	grams	1,248
T.D. ELOGATION @ YIELD	D 882	%	4.74
T.D. TENSILE @ 5%	D 882	grams	1,245
T.D. TENSILE @ 10%	D 882	grams	1,136
T.D. TENSILE @ 25%	D 882	grams	1,065
C.O.F. - (IN / IN)	D 1894	-----	.54
C.O.F. - (OUT / OUT)	D 1894	-----	.50

Example 7 (stretched)

PROPERTY	ASTM TEST #	UNITS	5.0 : 1
YIELD	-----	in ² /lb	33866
GAUGE	D 2103	mils	0.91
LIGHT TRANSMISSION	D 1003	%	22.2
GLOSS - (A SIDE)	D 2457	%	10.8
GLOSS - (B SIDE)	D 2457	%	11.4
DART DROP	D 1709	grams	112
MVTR (UPRIGHT / INVERTED)	E 96B/E96BW	g/m ² /day	3,779 / 4,077
M.D. STRIP GAUGE	D 2103	mils	0.91
M.D. TENSILE @ BREAK	D 882	grams	2,742
M.D. ELONGATION	D 882	%	46
M.D. TENSILE @ 5%	D 882	grams	425
M.D. TENSILE @ 10%	D 882	grams	805
M.D. TENSILE @ 25%	D 882	grams	1,822
M.D. SECANT MODULUS	D 882	p.s.i	23,860
T.D. STRIP GAUGE	D 2103	mils	0.92
T.D. TENSILE @ BREAK	D 882	grams	255
T.D. ELONGATION	D 882	%	410
T.D. TENSILE @ 5%	D 882	grams	80
T.D. TENSILE @ 10%	D 882	grams	126
T.D. TENSILE @ 25%	D 882	grams	177
T.D. ELOGATION @ YIELD	D 882	%	33
T.D. TENSILE @ YIELD	D 882	grams	179
T.D. SECANT MODULUS	D 882	p.s.i.	8,152
C.O.F. - (A / A)	D 1894	-----	0.29
C.O.F. - (B / B)	D 1894	-----	0.32

100-447-091450
10
15
The results in the Tables labeled Examples 3-5 demonstrate that the multilayer films produced according to this invention exhibit a good moisture vapor transmission rate. All of the
5 films exhibited a moisture vapor transmission rate of 270 to 4077 g/m²/24hr.

The films also exhibited good mechanical characteristics. The tensile strength, elongation, and modulus were sufficiently high such that the material can be used as a component of a reinforced surgical gown. In particular, the tensile strength, elongation, and modulus were significantly higher than those of conventional materials, such as polyethylene, which are used for surgical gowns.

The films exhibited a high puncture resistance as measured by the dart drop test. A high puncture resistance is desirable because during a surgery, if the material is punctured,
20 microorganisms would be able to penetrate the material and infect the medical personnel.

The light transmission test demonstrates that the films blocked more than about 60% of the light, which is desirable to hide the individual
25 or object covered by the film material.

The films exhibited a secant modulus in a range which provides adequate softness, drapability and comfort.

5 A biological penetration test was performed by Nelson Laboratories, Inc. (Salt Lake City, UT) on some of the films of Examples 3 and 5, using ASTM ES22 (now ASTM F1671). Three samples of each sample film were tested. The ES22 test is a live microorganism penetration test

10 Two films of Example 3, stretched at a draw ratio of 4:1, and 4.95, passed the blood barrier test ASTM ES 22

15 A biological penetration test was performed by Nelson Laboratories, Inc. (Salt Lake City, UT) on some of the films of Examples 3-5, using ASTM ES21 (now ASTM F1670). Three samples of each sample film were tested. The ES21 test is a blood penetration test

20 The stretched films of Example 3, at a draw ratio of 4.5:1 and 4.95:1 passed the ES21 test. The stretched films of Example 4, at a draw ratio of 4:1 and 4.25:1 did not pass. It is believed that the size of the particulate filler was too great for the thin films of Example 4 and therefore the large particles penetrated the surrounding layers. The stretched films of Example 5 at a draw ratio of 4.5: and 4:1 passed.

25
30 From the above data, the percentage of microvoids formed was calculated using the following formula:

$$\% \text{ Voids} = \frac{(\text{Yield Factor})_{\text{Actual}} - (\text{Yield Factor})_{0\% \text{ Voids}}}{(\text{Yield Factor})_{\text{Actual}}}$$

The results of the calculations are shown in the following tables.

% Voids Calculation for Example 3

Actual Yield (in ² /lb)	Actual Gauge (mils)	Yield Factor (in ² /lb)	Draw Ratio	% Voids (%)
12469	1.6	19950	1:1	0
41299	0.69	28496	4.5:1	30
43765	0.63	27572	4.75:1	27.6
40956	0.71	29079	4.95:1	31.4

% Voids Calculation for Example 4

Actual Yield (in ² /lb)	Actual Gauge (mils)	Yield Factor (in ² /lb)	Draw Ratio	% Voids (%)
15960	1.25	19950	1:1	0
54135	0.52	28150	4:1	29.1
57082	0.49	27970	4.1:1	28.7
61027	0.48	29293	4.25:1	31.9

% Voids Calculation for Example 5

Actual Yield (in ² /lb)	Actual Gauge (mils)	Yield Factor (in ² /lb)	Draw Ratio	% Voids (%)
9975	2.	19950	1:1	0
35113	0.83	29144	4:1	31.5
37024	0.75	27768	4.25:1	28.2
40905	0.69	28224	4.5:1	29.3

To demonstrate that the microporous layers can be stretched at greater draw ratios to form a greater volume percentage of voids, the Examples 6 and 7 were performed

% Voids Calculation for Example 6

Actual Yield (in ² /lb)	Actual Gauge (mils)	Yield Factor (in ² /lb)	Draw Ratio	% Voids (%)
8867	2.25	19950	1:1	0
38849	0.84	32633	5:1	38.9
39591	0.87	34444	5.25:1	42

% Voids Calculation for Example 7

Actual Yield (in ² /lb)	Actual Gauge (mils)	Yield Factor (in ² /lb)	Draw Ratio	% Voids (%)
8867	2.25	19950	1:1	0
33866	0.91	30818	5:1	35.3

While the invention has been described in detail and with reference to specific embodiments thereof, it will be apparent to one skilled in the art that various changes can be made therein without departing from the spirit and scope of the claimed invention.

CLAIMS:

1. A method of making a stretched, multilayer
breathable film having the combination of
properties of:

- (i) providing a barrier to
microorganisms; and
- (ii) providing a barrier to blood and
bodily fluids;

said method comprising the steps of:

(a) simultaneously extruding at least a
five-layer film from a die, said five-layer
film having as a minimum the following
structure:

C:A:B:A:C;

where B comprises a microporous core
layer containing at least one thermoplastic
polymer and at least one particulate filler;

C comprises an outer monolithic
layer containing a hydrophilic polymeric
resin capable of absorbing and desorbing
moisture and providing a barrier to
aqueous fluids and microorganisms, said
C layer being substantially free of
particulate filler; and

A comprises a microporous adhesive
layer for bonding said C layers to said
core layer B, wherein said C layer
substantially prevents the buildup of
particulate filler material on said die
during said extrusion step;

(b) stretching said extruded five-layer film
to thereby form micropores in said microporous
core layer and said microporous adhesive layer,

wherein said stretching step is conducted and said microporous core layer and said microporous adhesive layers have been formulated so as to provide micropores which allow the passage of gaseous water but substantially prevent the passage of liquid water.

2. A method according to claim 1, further comprising the step of combining a portion of the components comprising said B layer with a portion of the components comprising said C layers to form an adhesive mixture, and said extrusion step comprises extruding at least one A layer containing said adhesive mixture.

3. A method according to claim 1, further comprising the step of collecting scraps of said formed multilayer breathable film and said extrusion step comprises extruding at least one A layer containing said collected scraps.

4. A method according to claim 1, wherein said extrusion step comprises extruding said layers in the following volume ratio:

about 1 to about 40% by volume for each A layer;

about 1 to about 96% by volume for said B layer; and

about 1 to about 30% by volume for each C layer, the volume % being based on the total volume of said breathable film.

5. A method according to claim 1, wherein said extrusion step comprises extruding said

layers in the following volume ratio:

about 1 to about 10% by volume for each A layer;

about 60 to about 96% by volume for said B layer; and

about 1 to about 10% by volume for each C layer, the volume % being based on the total volume of said breathable film.

6. A method according to claim 1, wherein said extrusion step comprises extruding said layers in the following volume ratio:

about 1 to about 5% by volume for each A layer;

about 80 to about 96% by volume for said B layer; and

about 1 to about 5% by volume for each C layer, the volume % being based on the total volume of said breathable film.

7. A method according to claim 1, wherein said extrusion and said stretching steps are conducted so as to provide a breathable film having a thickness of about 1 mil or less.

8. A method according to claim 1, further comprising the steps of determining the volatile content in the materials for making said microporous core layer and said microporous adhesive layers; and

adjusting the amount of volatiles in said materials to provide micropores having an average diameter of about 1/8 to about 1/2 the thickness of the stretched microporous core layer or

stretched microporous adhesive layers.

5 9. A method according to claim 1, further comprising the steps of determining the water content in said particulate filler for making said microporous core layer and said microporous adhesive layers; and

10 adjusting the amount of water in said materials to provide micropores having an average diameter of about 1/8 to about 1/2 the thickness of the stretched microporous core layer or stretched microporous adhesive layers.

15 10. A method according to claim 8, wherein said adjusting step comprises adjusting the amount of volatiles in said particulate filler to be within a range of about 100 ppm to about 500 ppm, based on the weight of said filler particulate.

20 11. A method according to claim 8, wherein said adjusting step comprises adjusting the amount of volatiles in said particulate filler to be within a range of about 100 ppm to about 300 ppm, based on the weight of said filler particulate.

25 12. A method according to claim 1, wherein at least one of said microporous core layer and said microporous adhesive layers comprises a metallocene catalyzed linear low density polyethylene.

30 13. A method of making a stretched, multilayer breathable film having the combination of properties of:

- (i) providing a barrier to microorganisms; and
- (ii) providing a barrier to blood and bodily fluids;

5 said method comprising the steps of:

(a) simultaneously extruding at least a three-layer film from a die, said three-layer film having as a minimum the following structure:

10 C:D:C;

where C comprises an outer monolithic layer containing a hydrophilic polymeric resin capable of absorbing and desorbing moisture and providing a barrier to aqueous fluids and microorganisms, said C layer being substantially free of particulate filler; and

20 D comprises a microporous adhesive core layer for bonding said C layers together, wherein said C layer substantially prevents the buildup of particulate filler material on said die during said extrusion step;

25 (b) stretching said extruded three-layer film to thereby form micropores in said microporous core layer and said microporous adhesive layer, wherein said stretching step is conducted and said microporous core layer and said
30 microporous adhesive layers have been formulated so as to provide micropores which allow the combination passage of gaseous water but substantially prevent the passage of liquid water.

14. A multilayer breathable film having the of properties of:

(i) providing a barrier to microorganisms; and

(ii) providing a barrier to blood and bodily fluids;

said breathable film comprising at least five-layer film having as a minimum the following structure:

C:A:B:A:C;

where B comprises a microporous core layer containing at least one thermoplastic polymer and at least one particulate filler;

C comprises an outer monolithic layer containing a hydrophilic polymeric resin capable of absorbing and desorbing moisture and providing a barrier to water and microorganisms, said C layer being substantially free of particulate filler; and,

A comprises a microporous adhesive layer for bonding said C layers to said core layer B, wherein said C layer substantially prevents the buildup of particulate filler material on a die during formation of said multilayer breathable film, and wherein said micropores are constructed and arranged to provide the passage of gaseous water but substantially prevent the passage of liquid water.

15. A film according to claim 14, wherein at least one of said microporous adhesive layers comprises said thermoplastic polymer of said

microporous core layer and said hydrophilic polymeric resin of said monolithic layers.

5 16. A film according to claim 14, wherein said layers have the following volume ratio:

about 1 to about 40% by volume for each A layer;

about 1 to about 96% by volume for said B layer; and

10 about 1 to about 30% by volume for each C layer, the volume % being based on the total volume of said breathable film.

15 17. A film according to claim 14, wherein said layers have the following volume ratio:

about 1 to about 10% by volume for each A layer;

about 60 to about 96% by volume for said B layer; and

20 about 1 to about 10% by volume for each C layer, the volume % being based on the total volume of said breathable film.

25 18. A film according to claim 14, wherein said layers have the following volume ratio:

about 1 to about 5% by volume for each A layer;

about 80 to about 96% by volume for said B layer; and

30 about 1 to about 5% by volume for each C layer, the volume % being based on the total volume of said breathable film.

19. A film according to claim 14, wherein

said breathable film has a thickness of about 1 mil or less.

5 20. A film according to claim 14, wherein said microporous core layer or said microporous adhesive layers have been made by the steps of determining the volatile content in the materials for making said microporous core layer and said microporous adhesive layers; and

10 adjusting the amount of volatiles in said materials to provide micropores having an average diameter of about 1/8 to about 1/2 the thickness of the stretched microporous core layer or stretched microporous adhesive layers.

15 21. A film according to claim 14, wherein said microporous core layer or said microporous adhesive layers have been made by the steps of determining the water content in said particulate filler for making said microporous core layer and said microporous adhesive layers; and

20 adjusting the amount of water in said materials to provide micropores having an average diameter of about 1/8 to about 1/2 the thickness of the stretched microporous core layer or stretched microporous adhesive layers.

25 22. A film according to claim 14, wherein at least one of said microporous core layer and said microporous adhesive layers comprises a metallocene catalyzed linear low density polyethylene.

30 23. A film according to claim 14, wherein

said hydrophilic polymeric resin is selected from the group consisting of polyesters and polyamides.

24. A film according to claim 14, wherein said thermoplastic polymer comprises a polyolefin.

25. A film according to claim 14, wherein said thermoplastic polymer comprises a linear low density polyethylene.

26. A multilayer breathable film having the combination of properties of:

- (i) providing a barrier to microorganisms; and
- (ii) providing a barrier to blood and bodily fluids;

said breathable film comprising at least a five-layer film having as a minimum the following structure:

C:D:C;

where C comprises an outer monolithic layer containing a hydrophilic polymeric resin capable of absorbing and desorbing moisture and providing a barrier to water and microorganisms, said C layer being substantially free of particulate filler; and,

D comprises a microporous adhesive core layer for bonding said C layers together, wherein said C layer substantially prevents the buildup of particulate filler material on a die during formation of said multilayer

breathable film, and wherein said micropores are constructed and arranged to provide the passage of gaseous water but substantially prevent the passage of liquid water.

27. A film according to claim 26, wherein said layers have the following volume ratio:

about 1 to about 98% by volume for said D layer; and

about 1 to about 49% by volume for each C layer, the volume % being based on the total volume of said breathable film.

28. A film according to claim 26, wherein said layers have the following volume ratio:

about 80 to about 98% by volume for said D layer; and

about 1 to about 10% by volume for each C layer, the volume % being based on the total volume of said breathable film.

29. A film according to claim 26, wherein said layers have the following volume ratio:

about 90 to about 98% by volume for said A layer; and

about 1 to about 5% by volume for each C layer, the volume % being based on the total volume of said breathable film.

30. A medical gown comprising a multilayer breathable film according to claim 14.

31. A medical gown comprising a multilayer

breathable film according to claim 25.

ABSTRACT OF THE DISCLOSURE

Provided is a method of making a stretched, multilayer breathable film having the combination of properties of:

- (i) providing a barrier to microorganisms; and
- (ii) providing a barrier to blood and bodily fluids;

said method comprising the steps of:

(a) simultaneously extruding at least a five-layer film from a die, said five-layer film having as a minimum the following structure:

C:A:B:A:C;

where B comprises a microporous core layer containing at least one thermoplastic polymer and at least one particulate filler;

C comprises an outer monolithic layer containing a hydrophilic polymeric resin capable of absorbing and desorbing moisture and providing a barrier to aqueous fluids and microorganisms, said C layer being substantially free of particulate filler; and

A comprises a microporous adhesive layer for bonding said C layers to said core layer B, wherein said C layer substantially prevents the buildup of particulate filler material on said die during said extrusion step;

(b) stretching said extruded five-layer film to thereby form micropores in said microporous core layer and said microporous adhesive layer,


wherein said stretching step is conducted and said microporous core layer and said microporous adhesive layers have been formulated so as to provide micropores which allow the passage of gaseous water but substantially prevent the passage of liquid water. The invention also relates to a multilayer film.

5

Flow Plate Diagram

DESIGNED BY

Fig. 1



ZONE	REV	REVISION DESCRIPTION	DATE	BY
1				

FLOW PLATE PER DWG. No. 638487

FLOW PLATE PER DWG. No. 638487

DO NOT SCALE DRAWING		UNLESS OTHERWISE SPECIFIED		PROJECTION ANGLE	
X		+/- .05		ANGLE	
XX		+/- .015		ANGLE	
XXX		+/- .005		ANGLE	
ANGULAR		+/- 1/2 deg		DIMENSIONS ARE IN INCHES	
FRACTIONAL		+/- 1/64		SURF. FINISH 250 RMS	
THIS DRAWING AND ALL PARTS THEREOF IS AND SHALL REMAIN THE PROPERTY OF EGAN, DAVIS-STANDARD AND MAY NOT BE REPRODUCED FOR ANY PURPOSE WITHOUT THE CORPORATION'S WRITTEN CONSENT.					
DRAWN BY: SECHLER		DATE: 1/3/95		SIZE: PART NUMBER: B 638487	
REV. SHEET: 00		REV. SHEET: 01		REV. SHEET: 01	


EGAN® SOUTH ADAMSVILLE ROAD P.O. BOX 871 SOMERVILLE, N.J. 08876-0871 U.S.A. 1-808-722-6000	
DVG Davis-Standard Cremona & Knowles Corp.	
TITLE: PLATE, FLOW, LAYER, LAMNA	
C=10%A=20%B=40%A=20%C=10%	
FOREIGN TITLE	
SCALE: NONE	
ORIGINAL: 638487	

BLN	ITEM NO.	PCS	ITEM DESCRIPTION
4			

ABC
C = 10 %
A = 20 %
B = 40 %
A = 20 %
C = 10 %

Fig 2

Orientation




Standard Cost Embossed Extrusion Line

Standard
Casting Section

Walter F. Felt
7/21/95
Mills
Hawes 7/22/95

The process is being modified
to extrude & stretch the 5-Layer
Breathable Film in one step.



WINDER SECTION

PULL NIP STATION

TREATER STATION

CAST / EMBOSSING
SECTION

*Annealing or- heat setting

will initially be accomplished
by sending heated H_2O through the bored roll
above in the "pull nip section". We are investigating
and will most likely use IR heated idler rolls somewhere.

DRIVE SIDE


see option
#1 & 2 attached

annabwarp


Nick
Hawkins
7/21/95

A:B:C (103:202:403:208:102 Layer distribution by Volume)

Option #1



Option #2



many Chill rolls have random matte finish

- 240 RA

* H₂O Pan, & Wiper roll, may not be used if silicone roll doesn't stick to film.